SHIMOGA DIVISION.

ADVERTISEMENT.

The 27th May 1889

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Shimoga Division, up to 20th June 1889, for restoring Vadinhal Tank Register No. Channagiri Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1891.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Shimoga between the hours of 11 A. M. and 5 P. M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed, or specify ( ) per cent less than estimated rates.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for restoring Vadinhal Tank Register No. Channagiri Taluk", in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items of Work.	Quantity.	Rate.
Bund.—		
Earthwork raising bund	57,378	
Cutting grips	871	
Breach filling	5,912	
Puddling	179	
Old stone work	1,149	
New do	6,074	
Bench mark stones	2	
Grade stones	47	
Tank register stone	1	
Sluice No. I.—		
Earthwork	185	
Brick in mortar	838	
Plastering with mortar	5·78	
Covering slabs	118	
Vent floor and cross stones	L. S.	
Gibbet stones	2	
Plug with rod complete	1	
Date stone	1	
Sluice No. II.—		
Earthwork	206	
Brick in mortar	776	
Plastering with mortar	5·82	
Covering slabs	106	
Vent floor and cross stones	L. S.	
Gibbet stones	1	
Do gauge cut	1	
Date stone	1	
Plug with rod complete	1	
Waste Weir.—		
Brick in mortar	11,876	
Plastering with mortar	37·80	
Stone slabs 6" thick	4,973	
Rough stone work (new)	334	
Do (old)	100	
Concrete	721	
Earthwork excavation	1,250	
Do wing bund	1,500	
Improving draught	200	